

MILL AND OVERLAY RESTORATION LIMITS TO BE DETERMINED BY ENTITY PLAN CHECK, WITH FINAL LIMITS SET BY FIELD INSPECTOR. REFER TO DRAWINGS 500 SERIES.

REMOVE AND REPLACE EXISTING A.C. MATCH EXISTING DEPTH (PLUS ONE INCH).

EXISTING AGGREGATE BASE

PRIME COAT PER SECTION 408-PRIME COAT

2' MIN.

2' MIN.

CLSM MINIMUM DEPTH  
12" FOR MINOR COLLECTOR ROADWAYS (>OR=60', <80')  
24" FOR COLLECTOR AND ARTERIAL ROADWAYS (>OR=80')  
(NOT REQUIRED FOR TRENCH WIDTHS GREATER THAN 3-FT.)

95% MIN. COMPACTION TYPE II AGGREGATE BASE

\* CLSM NOT REQUIRED FOR RESIDENTIAL STREETS

MINIMUM TRENCH WIDTH IS RELATED TO DESIGN REQUIREMENTS AND SHALL BE INDICATED ON THE PLAN DRAWINGS. SEE SECTION 208-TRENCH EXCAVATION AND BACKFILL

INSTALLATION REQUIREMENTS INCLUDING CONTRACTOR TESTING AND FILL LIFTS SEE SECTION 208-TRENCH EXCAVATION AND BACKFILL

VARIES

GRANULAR BACKFILL OR SELECT BACKFILL OR BACKFILL WITH CONTROLLED LOW STRENGTH MATERIAL (CLSM) OR AS APPROVED BY THE ENGINEER SEE NOTE 1

DEPTH OF COVER IS RELATED TO DESIGN REQUIREMENTS AND SHALL BE INDICATED ON THE PLAN DRAWINGS. SEE SECTION 208-TRENCH EXCAVATION AND BACKFILL

COMPACTION PERCENTAGE PER GEOTECH ENG REQUIREMENTS OR MINIMUM OF 90%


REFER TO SECTION 208 REQUIREMENTS

PIPE ZONE

SEE SUBSECTION 208.03.14 FOR DEPTH OF PIPE COVER

90% MIN. COMPACTION IN PIPE ZONE, TYPE II OR TYPE III AGGREGATE BASE, SAND BACKFILL SEE NOTE 2

PIPE BEDDING SEE NOTE 3



PIPE OR BOX CULVERT

STABLE SUBGRADE

NOTES:

1. NO STONES OR LUMPS GREATER THAN 3" PERMITTED IN TRENCH 2' OR LESS IN WIDTH.
2. TRENCH WIDTH, BEDDING, SUBGRADE AND PIPE ZONE REQUIREMENTS FOR UTILITY INSTALLATIONS SHALL CONFORM TO THE RESPECTIVE ENTITY REQUIREMENTS.
3. CRUSHED ROCK MAY BE USED FOR PIPE BEDDING ONLY IF MATERIAL USE HAS BEEN SPECIFICALLY APPROVED BY THE GOVERNING AGENCY. SEE STANDARD DRAWING NO. 505 FOR PIPE BEDDING METHODS.
4. LAS VEGAS VALLEY WATER DISTRICT REQUIRES PIPE BEDDING AND BACKFILL WITHIN THE PIPE ZONE TO BE OF THE SAME MATERIAL.
5. A ONE INCH MAXIMUM LEVELING COURSE IS PERMITTED WHEN APPROVED BY THE ENGINEER.

SPECIFICATION REFERENCE

UNIFORM STANDARD DRAWINGS  
CLARK COUNTY AREA

208	TRENCH EXCAVATION & BACKFILL
302	AGGREGATE BASE COURSES

METHOD B FOR RIGID AND FLEXIBLE PIPE  
TRENCH BACKFILL - PAVED AREAS